

Tender for Providing and Fixing of Curtains including Dismantling & Disposal of Old Curtains in the NABARD, MP Regional Office Building, Bhopal



Part – II

Financial Bid Document For

**Providing and Fixing of Curtains including Dismantling &
Disposal of Old Curtains in the NABARD, MP Regional Office
Building, Bhopal**

**Tender for Providing and Fixing of Curtains including Dismantling & Disposal of Old Curtains in the NABARD, MP Regional Office
Building, Bhopal
Financial Bid**

I. Specifications of work

A. Curtain Cloth : Curtain cloth used in the work shall confirm to the following specifications.

- a. Fabric material : 100% Polyester Filament
- b. Usable Fabric width : 140 cm / 54"
- c. Martindale : not less than 12000 Rubs
- d. Weight : Not less than 300 GSM/Sqm
- e. Fabric density : Non Transperent Composition
- f. Colour and Print : Fast Colours, Assorted colours Plain and Prints, Beige, Cream, Light Brown, Light colour **as decided by Bank**
- g. Texture : Soft and smooth textured, good drapability & doobby
- h. Approved Brands : KC Fabrics, Homez, D'décor D'decor (Collection/ Quality — Ariel, Aura or similar)

If the quotation is for more than one brand, the brand with lowest rate will be considered.

B. Lining for Curtain Cloth : The lining for the curtain shall be in good quality Muslin Cotton Fabric. The contractors are advised to separately quote basic price of Lining Cloth per running metre of curtain. **Enclose Samples of Curtain Cloth with specifications.**

C. Stitching Specifications : The stitching of the curtains shall be modern, functional with Eyelet, Platter, etc. for easy sliding and maintenance. The curtains will be stitched as per site requirement with necessary modification in stitching as per site / size requirement. For fabricating Drapery heading, permanent finish buckram shall be double-folded into the heading (3 thicknesses of fabric) and sewn with either clear monofilament or triple-strand polyester thread, colour matched to the fabric used The bottom-of the buckram shall be sewn to the face of the fabric. Islets (1 ½ inch diameter with a ½ inch rim) or Islets (1 inch diameter with a 3/8 inch rim) shall be uniformly set across the heading, apart with the first and last from each end. Islets headers shall create a uniform, structured look that is both modern and functional presenting a clean look with built in hardware. Equidistant circles should be cut into the top of a draped fabric. Then circular metal islets should be secured within each one so that a curtain rod can slide right through with ease.

- a. Curtain to be stitched both sides if required / both ends.
- b. Upper side will have nefa with round cut Islets hole with click-clack Stainless Steel with bucrum lining (15-20 cm) to be supplied with curtain at 150-200 mm distance or as appropriate.
- c. Lower end to be stitched after double turn (nefa) to improve the fall of curtain. Lower nefa 150 mm to 200mm.
- d. Bottom hems are to be double-turned to consist of layers of fabric and be blind stitched.
- e. Side hems shall be double-turned 1 ½ inch wide and be blind stitched so that stitches are not visible on the face of the fabric. All vertical seaming shall be sewn with selvage trimmed and over locked.
- f. **Eyelet, Platter, and Simple stitching design will be got approved by the bank before starting the work.**

D. Hanging Arrangement : The bracket used for hanging the curtains shall be good quality Stainless Steel Brackets, shall be side mounted or front mounted or ceiling mounted as required at site. Curtain Rods shall be stainless steel pipe -1" (25 mm) diameter, 22 Gauge with steel grade 304 or higher, Robust structure, Excellent Seamless finish. The end caps shall be of stainless steel. Where curtain is used as a partition/ long length, sufficient support from ceiling should be provided to avoid sagging. All hardware used in the work shall be of good quality. **The samples of the brackets, pipe, end caps, eyelets, etc. and other hardware such as ceiling suspenders, fasteners, etc. is to be got approved before using the same in the work.**

II. Measurement of the work and basis of payment : The payment will be made on the basis of detailed measurement of the work done. The contractor will have to submit measurement sheets in tabular form clearly indicating the details of curtains fixed indicating their locations, numbers of curtains fixed along with the details of measurements of end to end finished length of the curtain in metres. **For payment, only the end to end length of the finished curtain in running metre will**

Tender for Providing and Fixing of Curtains including Dismantling & Disposal of Old Curtains in the NABARD, MP Regional Office Building, Bhopal

be measured. Cost of stitching, cost of hanging arrangement, all material and labour is to be included in the per metre cost of finished curtain. The contractors shall be paid all inclusive rates and nothing extra shall be paid on any other count.

III. Tenderer to visit the actual site : The tenderer is advised to visit the actual site and fully acquaint themselves with the site conditions, quantum of work, etc. before quoting their rates for this work. NABARD shall not be responsible in any way for non-familiarisation of site conditions. Once the tenderer has quoted the work, it implied that he has ascertained various site conditions and no claim, whatsoever, will be entertained by NABARD on any such account.

IV. Variation in Quantities : Before starting the work, the contractor will jointly visit the site along with the Bank's representative to identify the details of curtains required to be fixed indicating their locations, numbers of curtains required to be fixed and prepare estimate of quantities in tabular form clearly indicating the details of measurements of end to end finished length of the curtain in metres required to be fixed and get the same approved by the Bank before starting the work. Similarly, the curtains already fixed and required to be disposed off should be also recorded and got approved before removal. The quantities in the Schedule approximately indicate the total extent of work but may vary to any extent and may even be omitted thus altering the aggregate value of the Contract.

Bill of Quantity :

| Sl. No. | Description | Approx. Quantity | Unit | Brand of curtain Cloth | | | | | |
|---------|---|--------------------|----------|--|--------------|--|--------------|--|--------------|
| | | | | KC Fabrics | | Homez | | D'decor | |
| | | | | Rate per unit (Rs.) in figures & words | Amount (Rs.) | Rate per unit (Rs.) in figures & words | Amount (Rs.) | Rate per unit (Rs.) in figures & words | Amount (Rs.) |
| 1 | Providing & Fixing up of Window / Glazing / Door curtain in required sizes having the specification as detailed above. The rates shall be inclusive of the cost of the curtain cloth, Lining cloth, stitching, Hanging arrangement, Fixing of the curtain, dismantling and stacking of the old curtains and fixtures, including making good the damage to window/wall in removal of the old fixtures. The quoted rates shall include cost of all material, labour, Taxes and overheads. Nothing extra shall be paid and the contractor shall be liable to incur all the expenses required in satisfactory completion of the work. | 1300 running metre | metre | | | | | | |
| 2 | Buyback of old curtains and fixture fittings which are removed from the existing location. | 1 Job | Lump-sum | | | | | | |
| | Total Amount (In figures and in words). i.e., Amt. of Sl. No.1 (MINUS) Amt. of Sl. No.2 | | | | | | | | |
| | GST payable Tax Authorities | | | | | | | | |
| | Grand Total | | | | | | | | |

Tender for Providing and Fixing of Curtains including Dismantling & Disposal of Old Curtains in the NABARD, MP Regional Office Building, Bhopal

Specifications of Lining Cloth : _____

Basic Price of Lining Cloth : Rs. _____ per metre of finished length of curtain cloth.

Sample of Lining Cloth, enclosed : Yes/ No.

Declaration

I/We have read and understood all instructions/conditions and I/We have taken into account the above instructions/conditions while quoting the rates.

Seal and Signature of the contractor :

Place:

Date:

Name : _____

Address: _____
