



NB (Kerala)/ DPSP/2138/ SQ-66/ 2020-21

23 November 2021

Corrigendum

Tender for Undertaking Road taring work and Re-laying underground Drainage Water System in NABARD Gardens, Dr Pai Road, Poojapura, Thiruvanthapuram

Please refer to tender NB. Kerala/ DPSP/SQ-66/ 1913 /2021-22 dated 05th November 2021.

In this connection, we would like to inform you that

- i) The revised price bid indicating units for the items No. 1-7 under the “Re-laying of Underground Drainage Water System” is uploaded herewith. The same to be filled and submitted in third envelope as indicated in the tender.
- ii) The last date for submission of the Quotations has been extended till 13:00 PM, 30 November 2021 and the tender will be opened at 15:00 on 30 Nov 2021.

There is no other change in the quotation terms and conditions.

Yours Faithfully

K Ramalingam
Deputy General Manager

राष्ट्रीय कृषि और ग्रामीण विकास बैंक

National Bank for Agriculture and Rural Development

केरल क्षेत्रीय कार्यालय

राष्ट्रीय कृषि और ग्रामीण विकास बैंककेरल क्षेत्रीय कार्यालय , पुन्नेन रोड ,स्टाट्यू, तिरुवनंतपुरम - 695001 टेलि: 0471 2701600/700 ई-मेल: trivandrum@nabard.org

Kerala Regional Office

National Bank for Agriculture and Rural Development, Kerala Regional Office ,Punnen Road, Statue Thiruvananthapuram – 695001

Tel :- 0471 2701600/2701700 • E-mail: trivandrum@nabard.org



PART- II
PRICE BID

**Tender for Undertaking Road taring work and Re-
laying Underground Drainage Water System in
NABARD Gardens, Dr Pai Road, Poojapura,
Thiruvanthapuram**

SCHEDULE OF QUANTITIES
(Rate to be quoted in this sheet only)

This is an item rate tender. The Amount quoted shall be firm and shall include all costs, allowances, Transportation, taxes, levies, Works Contract tax and excluding GST (Which should be quoted separately). The rates quoted for each and every item should be self-sustaining and reasonable.

Sl. No.	Description of work	Quantity	Unit	Rate	Amount
I	Taring of Road	A		B	AXB
1	Providing and applying tack coat using hot straight run bitumen of grade VG-10 (conforming to IS: 73, 2013) including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications. Laying 2.5 cm premix carpet surfacing with 3 cum of stone chippings of 12 mm nominal size per 100 sqm and bitumen emulsion (medium setting min 65% of bitumen contents), complying with IS:8887, using 96 kg per cum of chippings, including consolidation with road roller of 6 to 9 tonne capacity etc.	680	m ²		
2	Providing and laying seal of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg of bitumen per cum of fine aggregate and 0.60 cum of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete.	680	m ²		
	TOTAL				
	GST				
	Grant Total with GST(A)				

II		Re-Laying of Underground Drainage Water System			
1	Providing and laying cement concrete using 20mm nominal size graded aggregate including compaction, finishing the top surface to level complete as directed	6	m ³		
2	Cutting full grout macadam road surfaces including W.B.M inclusive of cost of placing PCC 1:2:4 of required thickness by using 20mm nominal size aggregate, compacting, curing etc.	60	m ²		
3	Demolishing PCC work for laying pipe lines including stacking of serviceable materials.	10	m ³		
4	Removing & rearranging interlocking paver blocks flooring with manufactured sand/stone chips bed including stacking of serviceable materials.	25	m ²		
5	Supply, Laying and Fixing in Position PVC drainage pipes of approved make including fitting & accessories as required by the site, cutting pipes to required length, necessary excavation, testing etc.				
5(i)	110mm-4inch 3.2mm thick type B pipe	85	m		
5(ii)	160mm 6 inch, 4mm thick type B pipe	300	m		
6	Providing and fixing PVC gully trap of approved make, including connection with PVC soil/waste pipe embedded in CC 1:4:8 using 20mm metal, encased in a chamber of 300mm built with 115mm brick masonry in CM 1:3 over a bed of CC 1:4:8 using 20mm aggregate 100mm thick, plastering with CM 1:3 finished smooth and fixing CI frame and cover of size 300mm*300mm	40	Each		
7	Construction of manhole of internal dimension 600*600mm	6	Each		

in 230mm thick brick wall in CM 1:3 over a bed of 150mm thick PCC 1:2:4, plastering with CM 1:3 finished smooth, fixing CI frame and cover of size 600mm*600mm and encasing of sewer connections to manhole in PCC 1:2:4				
TOTAL				
GST				
Grand Total with GST(B)				
TOTAL(A+B)				

Grand Total Amount without GST (In Words).....

Grand Total Amount with GST (In Words).....

Note:

1. The basic rate means the market price of the material. The contractor has to submit the bill of authorised dealer from whom procurement of material is done by the contractor in respect of items for the basic rate has been mentioned in the Price Bid. The permissible variation in basic rate will be 5% in the mentioned value beyond that necessary deduction/extra payment will be made to contractor as applicable.
2. The tenderers should visit work site and assess site conditions and scope of work before quoting the rates.
3. Rates are to be quoted inclusive of all prevailing taxes like GST, etc as per scope of the work and after visiting the site.
4. The contractor shall include all prevailing taxes like GST etc. in the quoted rates as stated in the Clause of General Instruction of the Technical bid.
6. The contractor has to quote for all the items of the tender. Incomplete tenders and tenders without EMD will be rejected.

Accepted all terms & conditions of technical & price/financial bid



Place:

Date :

Address of the contractor:

Name & Seal:

(Signature of the Tenderer)