

Schedule of Quantities

**Provision of Digital EPABX System with connected wiring etc in NABARD
Abasan, RNC Road, Tangra, Kolkata-15**

Sr No:	Particulars/Description	Unit	Quantity	Rate	Amount
1	Supply, Installation, Testing & Commissioning of DIGITAL ISDN IP EPABX system having 100 lines capacity of reputed make like Matrix, Samsung, Panasonic etc as per the manufacturer's specifications etc.	Set	1.00		
2	Supply, laying, testing of finolex or equivalent voice cables of different sizes/pairs :- 20 Pairs.	Metre	200.00		
3	Supply, laying, testing of finolex or equivalent voice cables of different sizes/pairs :. 25 Pairs	Metre	90.00		
4	Supply, laying, testing of finolex or equivalent voice cables of different sizes/pairs :. 50 Pairs	Metre	70.00		
5	Supply, laying, testing of finolex or equivalent voice cables of different sizes/pairs :. 01 Pairs	Metre	2520.00		
6	Supply, laying, testing of finolex or equivalent voice cables of different sizes/pairs :. 10 Pairs	Metre	400.00		
7	Supply, laying, testing of 20 mm dia PVC of reputed make conduits for voice cables of different sizes including fixing with saddles etc	Metre	1000.00		
8	Making trenches underground for taking voice cables in conduits of 25 mm size PVC of reputed make, finishing the trench with cement Mortar, curing etc complete as directed.	Metre	300.00		
9	Supply, fixing and testing of Junction Box in Ground or upper floors as directed.	No:	4.00		
10	Supply, fixing and testing of	No:	50.00		

	Telephone instruments of Beetle, Panasonic or equivalent make as directed. The instrument should have number display arrangement as also call forward system from One point to individual flats.				
11	Supply and fixing of 15/5 Amp Power points near digital EPABX system including flat conduit wiring (2.5 sqmm) etc complete as directed.	No:	4.00		
Total amount in Rs					

GST as applicable extra

Place : Kolkata

Sign, name and address of the Contractor

Date :